

## Step 1

Step 2 Position (2) middle panels (closed hole sockets) on 12" legs in floor panel

overhanging outside edge of panel as

shown.

## Step 3

Position top panel (closed hole sockets) on 24" legs using outside rows of sockets as shown. Push panel down until legs are fully seated in sockets.

Lay (2) floor panels (open hole sockets) in position and place 12" and 24" legs as shown. (Make sure legs go through to ground).

## Structural Plastics

- 3401 Chief Drive - Holly, Michigan 48442-9333 - Phone (810) 953-9400 - Fax (810) 953-9440 **1-800-523-6899** sm36-66-962403p\_inst/0299